

CONTRACTOR

Thornton Building & Restoration Ltd

Unit 14, Holbeck Urban

Village

Leeds, LS11 9NT

United Kingdom

Tel: 0113 246 8800

admin@thorntonbr.co.uk

CLIENT

Whitfield Estate Management Ltd

Attn: Mr. Richard Ashworth,

Facilities Director

12 Grosvenor Gardens

London, SW1W 0DH

United Kingdom

r.ashworth@whitfieldestate.co.uk

QUOTE REFERENCE

QT-4892

Issue Date: 6 February 2025

Valid Until: 7 April 2025

Validity: 60 days

PROJECT ADDRESS

Whitfield House, 88–92 Cannon Street,
London EC4N 6HA

PROJECT TYPE

Office Refurbishment —
Floors 2 & 3

CURRENCY

GBP (£)

We are pleased to present this quotation for the full internal refurbishment of the second and third floors of Whitfield House, Cannon Street. Works include suspended ceiling replacement, full redecoration, LVT flooring installation, partition reconfiguration, and electrical first and second fix. All prices are exclusive of VAT at the standard rate of 20%.

SCHEDULE OF WORKS

#	ITEM / TRADE	UNIT	QTY	RATE (£)	AMOUNT (£)
1	Strip out — removal of existing ceiling tiles, partitions, carpet, fittings to skip	Item	1	1,850.00	1,850.00
2	Suspended ceiling — Armstrong Ultima 600×600 tile system, complete installation	m²	460	32.00	14,720.00
3	LVT flooring — Amtico Spacia (client-specified), supply and fit incl. DPM	m²	460	28.50	13,110.00
4	Stud partition reconfiguration — new meeting room pod (12m²) and breakout area	Item	1	3,200.00	3,200.00
5	Full decoration — plaster skim, mist coat, two coats emulsion (walls & ceilings)	Item	1	4,100.00	4,100.00
6	M&E first and second fix — lighting, power, data containment per layout drawing	Item	1	6,500.00	6,500.00
7	Glazed manifestation film to meeting room partitions (logo pattern, client-supplied artwork)	m²	18	85.00	1,530.00

#	ITEM / TRADE	UNIT	QTY	RATE (£)	AMOUNT (£)
8	Project management, site supervision, welfare, and waste disposal	Weeks	4	875.00	3,500.00

Net Total (ex. VAT) £ 28,510.00

VAT @ 20% £ 5,702.00

TOTAL INC. VAT £ 34,212.00

(Quote base amount excl. VAT: £28,510)

TERMS & CONDITIONS

PAYMENT TERMS

Monthly interim valuations. 30-day payment terms from invoice date. 5% retention released 6 weeks post practical completion.

EXCLUSIONS

Asbestos surveys and removal. Structural engineer's fees. Client-supplied furniture installation. Fire alarm modifications beyond zone extension.

PROGRAMME

4-week programme commencing within 2 weeks of written instruction. Works to be carried out during normal business hours unless agreed otherwise.

INSURANCE

Thornton B&R carries £5m public liability insurance. Contractor's all-risk insurance included for works value. Certificates available on request.

DETAILED ROOM-BY-ROOM BREAKDOWN

Floor 2 — Open-Plan Office (approx. 240 m²)

Ceiling tile replacement (Armstrong Ultima, 240 m²)	£ 7,680.00
LVT flooring supply and fit (240 m²)	£ 6,840.00
Redecoration walls & soffits	£ 2,100.00
Electrical works — LED luminaire replacement (40 No.) & power distribution	£ 3,400.00

Floor 2 — New Meeting Room Pod (12 m²)

Stud partition, insulation, plasterboard and skim	£ 1,950.00
Glazed manifestation (10 m²)	£ 850.00
Solid core door, frame and ironmongery	£ 680.00
Decoration, floor and ceiling — meeting room	£ 520.00

Floor 3 — Open-Plan Office (approx. 220 m²)

Ceiling tile replacement (220 m²)	£ 7,040.00
LVT flooring supply and fit (220 m²)	£ 6,270.00
Redecoration walls & soffits	£ 1,800.00
Electrical works — data containment, power distribution	£ 3,100.00

Floor 3 — Breakout Area (approx. 28 m²)

Partition reconfiguration and decoration	£ 1,250.00
Glazed manifestation (8 m²)	£ 680.00
Specialist pendant lighting feature (3 No.)	£ 950.00

Common Areas (Lift Lobby, Corridors, WCs)

Strip-out, redecoration and minor flooring works	£ 1,200.00
WC refurbishment — tiling, sanitary ware renewal	£ 2,200.00

SUBMITTED BY
Thornton Building & Restoration Ltd

ACCEPTED BY
Whitfield Estate Management Ltd

Authorised Signature & Date

Authorised Signature & Date